

Figure: 25 TAC §289.229(h)(2)(A)(i)

TABLE I

| System | Measurement Location | Leakage Limit |
|-----------------|---|----------------------------------|
| 5-50 kV | 5 centimeters (cm) from the tube housing assembly | 1 milligray (mGy) in 1 hour (hr) |
| >50 and <500 kV | 1 meter (m) from the target | 1 cGy in 1 hr |
| | 5 cm from the tube housing assembly | 30 cGy in 1 hr |